

Workplace: Branch Locations throughout Australia								e: 1 of 7
TASK / OPERATION	Safe Wor	rking at Heig	Overall Risk Rating After	4 Acute	<b>3 H</b> ig			
					Controls	2 Moderate	<b>1 L</b> o	
Personal Protective Eq	uipment							
	Foot	Head	Hearing	High	Eye	Hand		
	Protection	Protection	Protection	Visibility	Protection	Protection		
		EV			6			
lormal Requirements: Safety footwear, hard	hat.							
As Required: Hearing protection, h hand protection (glove	• •	hirt or vest, sun pro	tection (broad bi	im hat, sun so	creen, tinted sa	afety glasses), eye	e protection (	goggles
Safety Notes								
<ol> <li>Falling from height can c</li> <li>Fall protection should be manhole or lift well.</li> </ol>				n could fall or	nto/into someth	ing dangerous. E	xample – An	open

Sequence	Potential Hazards or Risks of Each Step.	RB	Control Measures - Actions to be Taken	RA	Responsible officer
	NC	DTE: RE	B = Risk Rating before controls implemented - RA = Risk Rating after ca	ontrols ar	e implemented.
Employee requirements	Legislation breach. Use of untrained operators. Incorrect use of fall arrest systems. Unable to perform rescue procedures. Unknown site hazards.	2M	<ul> <li>Training:</li> <li>Should include:</li> <li>Legislative Requirements.</li> <li>Safe work procedures.</li> <li>Fitting of personal protective equipment.</li> <li>Recognition and control of falling hazards.</li> <li>Nature of fall hazards within the work area.</li> <li>Correct procedures for erecting, maintaining, disassembling and inspecting fall arrest systems.</li> <li>Correct fitting of the harness Incorrectly fitted harnesses can cause serious injury in the event of a fall.</li> <li>Limitations of the equipment.</li> <li>Rescue procedures in the event of a fall.</li> <li>Correct procedure for handling equipment and materials while working at heights</li> <li>Manual handling.</li> <li>Site induction.</li> </ul>	1L	
Risk Assessment	Personal injury. Falls. Stress and Strain. Electric shock. Legislation breach.	2M	<ul> <li>Hazards to be assessed: Height of work.</li> <li>Ground hazards – rocks, reinforcing steel etc.</li> <li>Lack of guard rails or other edge protection.</li> <li>Pitch of roof (if relevant).</li> <li>Surface materials – brittle sheeting.</li> <li>Weather conditions – high winds (Example – erecting directional signs outdoors.)</li> <li>Use of power tools (location of leads, congestion in work area etc.)</li> </ul>	1L	

Authorised by OHS Training & Consultancy Services

Sequence	Potential Hazards or Risks of Each Step.	RB	Control Measures - Actions to be Taken	RA	Responsible officer
	N	DTE: RE	B = Risk Rating <b>before</b> controls implemented - <b>RA</b> = Risk Rating <b>after</b> co	ntrols ar	e implemented.
Risk control order	Legislation breach.	2M	<ul> <li>Provision and maintenance of:</li> <li>1. Secure stable work platform.</li> <li>2. Secure perimeter screens, fencing or handrails or other forms of physical barriers.</li> <li>3. Other forms of restraint such as harnesses, lanyards etc.</li> </ul>	1L	
Planning	ingPersonal injury. Slips and Falls. Struck by falling objects.Lack of warnings of overhead work being carried out.		<ul> <li>General - Identify:</li> <li>All tasks that could involve someone falling – Example – working within 3 metres of a roof edge.</li> <li>Any objects that could fall onto someone.</li> <li>Possible adverse climate conditions – Example rain or heavy dew.</li> <li>Risks to other workers on site Example – objects that could fall onto others.</li> <li>Warning signs and/or barricades must be in place where persons:</li> <li>Can gain access to the work area if any part of the work area is known to be incomplete, unsound, fragile or brittle.</li> <li>There is a risk of anyone being injured by materials or equipment falling from above.</li> </ul>	1L	

Sequence	Potential Hazards or Risks of Each Step.	RB	Control Measures - Actions to be Taken	RA	Responsible officer
	NC	DTE: RE	B = Risk Rating before controls implemented - RA = Risk Rating after co	ontrols ar	e implemented.
Site Awareness	Personal injury. Falls. Stress and Strain. Electric shock.	2M	<ul> <li>Review where applicable: <ul> <li>Availability and effectiveness of fall prevention equipment.</li> <li>Crane placement schedule – If relevant to the job.</li> <li>Access to the work area (Example – roof) and</li> <li>Any personal protective equipment.</li> </ul> </li> <li>Locate: <ul> <li>Any existing power cables, water pipes, air conditioning ducts etc. prior to work commencing.</li> </ul> </li> </ul>	1L	
Preparations - Scaffolding	Personal injury. Falls. Stress and Strain. Electric shock. Legislation breach.	ЗН	<ul> <li>Fall arrest scaffolding:</li> <li>When required fall arrest scaffolding should be installed around the perimeter of the building.</li> <li>Fall arrest scaffolding will: <ul> <li>(a) be unobstructed and at least 675 mm wide for the length of the platform;</li> <li>(b) be able to withstand the impact of a fall onto it; and</li> <li>(c) have edge protection erected: <ul> <li>i. along the outer edge of the length of the platform; and</li> <li>ii. along the edges of each end of the fall arresting platform.</li> </ul> </li> <li>Mobile scaffolding:</li> <li>Mobile scaffolding must be positioned as close as practicable to the underside of the roof and not more than two metres below the working surface.</li> </ul> </li> </ul>	2M	

Sequence	Potential Hazards or Risks of Each Step.	RB	Control Measures - Actions to be Taken	RA	Responsible officer
	NC	DTE: RE	<b>B</b> = Risk Rating <b>before</b> controls implemented - <b>RA</b> = Risk Rating <b>after</b> co	ontrols ar	e implemented.
Preparations - Electricity		ЗН	<ul> <li>Power cables:</li> <li>Depending upon the risk of electrocution to on site workers (roof workers, crane operators, labourers etc.) the following must be considered: <ol> <li>"Tiger Tails" can be installed. (Note: Tiger tails ONLY give a visual warning of the proximity of power lines.)</li> </ol> </li> <li>Power cables can be redirected or power isolated for the duration of the work.</li> </ul>	2M	
Preparations - Ladders	Personal injury. Slips and falls. Stress and strains. Electric shock.	2M	<ul> <li>Ladders:</li> <li>All ladders must be: <ol> <li>Identifiable as being of commercial quality.</li> <li>Inspected before use and periodically there after.</li> <li>Removed from use immediately if damaged.</li> <li>Have non slip feet and be secured at the top.</li> <li>Elevated at an appropriate angle. (Horizontal distance from base to vertical plane of support should be one-quarter the ladder height.)</li> <li>Extend to at least one metre above the stepping off point.</li> <li>Positioned away from power lines.</li> </ol> </li> <li>Note: <ul> <li>Employees must NOT carry tools while climbing or descending ladders.</li> </ul> </li> </ul>	1L	

Sequence	Potential Hazards or Risks of Each Step.	RB	Control Measures - Actions to be Taken	RA	Responsible officer
	N	IOTE: RE	B = Risk Rating before controls implemented - RA = Risk Rating after co	ontrols ar	e implemented.
Daily Checks	Personal injury. Falls.	3H	<ul> <li>Ensure:</li> <li>Scaffold is erected as per the plan (where required).</li> <li>All bracing used is as per the manufacturers specifications.</li> <li>All guard rails, mid rails and toe boards are in place to prevent a person falling. (2 m or more.)</li> <li>There are no damaged planks. If found they must be removed from the site.</li> <li>Suitable access ways to working platforms.</li> <li>Working platforms are fully planked.</li> <li>Scaffold is suitably tied to prevent collapse from load or wind.</li> </ul>	2M	
Site Safety		2M	<ul> <li>Work areas must be kept clean and tidy.</li> <li>There MUST be a safe system for collecting, storing and disposing of waste materials.</li> <li>Rubbish and other items should not be thrown from the roof to the ground.</li> <li>A safe means of removal must be used such as placing waste in skips and having a general clean up once a day.</li> </ul>	1L	

## **References:**

Tasmania – Play it safe – Working at Heights – A guide to reducing the risk of injury while working.
Queensland – Workplace Health and Safety – Rural Plant Code of Practice 2004.
New South Wales – WorkCover - Safe Working at Heights – Guide 2006.
United States Department of Labor – OSHA – Fall protection.
SafetyCulture – Safe Work Procedure – Working on Roofs.
SafetyCulture – Safe Work Procedure – Elevating Work Platforms.
SafetyCulture – Safe Work Procedure – Ladders – Safe Use.
SafetyCulture – Safe Work Procedure – Trestles – Safe Use.
SafetyCulture – Safe Work Procedure – Scaffolding.